ADA 130384

2301



CENTER

LABORATORY

TECHNICAL REPORT

NO. 12593

LIGHTWEIGHT COMPOSITE TOW BAR

Contract Number DAAK30-79-C-0111 June 1981



Robert Adkinson
Exxon Enterprises
Greer, South Carolina 29651
And
T. Wassel, D. Ostberg & M. Holly
US Army Tank Automotive Command

ATTN: DRSTA-RCKM

by

Warren, MI 48090

Approved for Public Release: Distribution Unlimited.

U.S. ARMY TANK-AUTOMOTIVE COMMAND RESEARCH AND DEVELOPMENT CENTER Warren, Michigan 48090

20030908025

NOTICES

The findings in this report are not to be construed as an official Department of the Army position.

Mention of any trade names or manufacturers in this report shall not be construed as advertising nor as an official indorsement or approval of such products or companies by the US Government.

Destroy this report when it is not longer needed. Do not return to the originator.

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

. REPORT DOCUMENTATION	READ INSTRUCTIONS BEFORE COMPLETING FORM			
1. REPORT NUMBER	3. RECIPIENT'S CATALOG NUMBER			
12593				
4. TITLE (and Subtitle)		5. TYPE OF REPORT & PERIOD COVERED		
4. III LE (and Submite)		THE OF REPORT & LINES SOTEINED		
·	,			
		5. PERFORMING ORG. REPORT NUMBER		
Lightweight Composite Tow Bar				
7. AUTHOR(e)		8. CONTRACT OR GRANT NUMBER(#)		
·				
	!			
Robert Adkinson - Exxon Enterprises		DAAK30-79-C-0111		
9. PERFORMING ORGANIZATION NAME AND ADDRESS		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS		
Exxon Enterprises, Greer, South Ca	·14 20681			
<u> </u>	erolina 29651	<u> </u>		
11. CONTROLLING OFFICE NAME AND ADDRESS US Army Tank-Automotive Command		12. REPORT DATE June 81		
Warren, MI 48090, ATTN: DRSTA-RCK	M	13. NUMBER OF PAGES		
Project Engineers: T. Wassel, D. (
14. MONITORING AGENCY NAME & ADDRESS(If different		15. SECURITY CLASS. (of this report)		
,				
	!	Unclassified		
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE		
		SCHEDULE		
16. DISTRIBUTION STATEMENT (of this Report)				
Approved for Public Release:				
Distribution Unlimited.				
		•		
17. DISTRIBUTION STATEMENT (of the abstract entered	in Block 20, it different tro	an Report)		
	•			
		•		
18. SUPPLEMENTARY NOTES		!		
÷				
_		•		
19. KEY WORDS (Continue on reverse side if necessary and	d identify by block number)			
, , , , , , , , , , , , , , , , , , , ,	, _ ,			
Tow Bar		!		
Graphite Fiber Reinforced Epoxy		1		
Filament Winding				
Adhesive Bonding Organic	c Composites			
20. ABSTRACT (Continue on reverse side if recovery and	I identify by block number)			
This program was initiated to develop a lightweight military standard heavy				

This program was initiated to develop a lightweight military standard heavy duty tow bar manufactured from organic composites. A tow bar weighing 125 lbs (vs 340 lbs for standard tow bar) was successfully designed and fabricated from graphite reinforced epoxy tube adhesively bonded to lightened steel end fittings. A kevlar overwrap was utilized over the graphite epoxy tubes to prevent cutting and damage.

OVER

SECURITY CLASSIFICATION OF THIS PAGE(When Date Entered)

20. ABSTRACT Cont.

The fabricated tow bars were tested at Aberdeen Proving Ground in order to obtain a safety release. Although a safety release was not obtained, the concept demonstration of a lightweight composite tow bar was proven feasible. A modified tow bar with higher temperature capability adhesive will be fabricated in a follow on program. Results of the APG tests are listed in APG report no. APG-MT-5578.

SUMMARY

The lightweight composite tow bar program, under contract number DAAK-30-79-C-0111, was to demonstrate the producibility of a tow bar, made with a composite of materials, weighing only 125 pounds (56.7 kg). The current metallic tow bar weighs approximately 340 pounds (154.2 kg.). If producible, a composite material 125 pound tow bar would facilitate tow bar use, and require fewer personnel for deployment.

We produced two tow bars, each weighing slightly less than 125 pounds, with steel fittings and attaching hardware.

The US Army Tank-Automotive Command (TACOM), in September, 1979 granted authorization for the preliminary design phase. One production design composite tube was delivered to TACOM for laboratory testing. In March, 1980 TACOM approved the design and requested the fabrication of prototype tow bars. Two tow bars were delivered in December, 1980.

The prototype tow bar is 83-1/2 inches (2121 mm) long from eye to eye; this does not include the clevis fittings. Figure 1 shows the finished tow bar just before their shipment to the Army. Note in the photograph that the prototype tow bar is similar in outward appearance to the current metallic tow bar. The big difference is that the metallic tow bar weighs approximately 340 pounds compared to the approximate weight of 125 pounds for the composite one.

By using composite materials, a lightweight tow bar has been fabricated which meets the requirements specified in the contract. Field testing, which is to follow, will be used to validate both the concept and the design.

TABLE OF CONTENTS

SECTION		PAGE
	SUMMARY	2
1.0	INTRODUCTION	6
2.0	DESIGN DISCUSSION	
2.1	Design Criteria	9
2.2	Material Considerations	10
2.2.1	The Composite Tubes	10
2.2.2	The Metal Fittings	15
2.2.3	Adhesive Material Selection	15
2.3	Tow Bar Design	15
2.3.1	Composite Tube Design	15
2.3.2	Design of the Metal Parts	18
2.3.3	Adhesive Joint Design	24
2.5.5	Rangeliae April Degrigues	€ -1
3.0	ANALYSIS	30
3.1	Finite Element Analysis of the Adhesive Joint	30
3.2	Tow Bar Analysis by Component	54
3.2.1	Composite Tube Analysis	55
3.2.2	Steel Sleeve	57
3.2.3	Weld Joint	57
3.2.4	Eye	58
3.2.5	Lunette	59
3.2.6	Clevis	60
4.0	FABRICATION	69
4.1	Metal Fittings	69
4.2	Composite Tube	69
4.2.a	Kevlar Sheath	69
4.2.b	Graphite/Epoxy Tube	69
4.3	Weld Assembly	75
4.4	Final Assembly	76
5.0	mpometric.	777
5.0	TESTING	77
5.1	Material Testing	77 77
5.1.a	Graphite/Epoxy	77
5.1.b	Adhesive	77
5.2	Joint Tests	78
5.3	Design Verification	79
5.4	Non-Destructive Testing	79
5.5	Field Testing	80
ADDENDUM.	***************************************	81
	N ITST	114

LIST OF ILLUSTRATIONS

FIGURE	TITLE	PAGE
1	Composite Tow Bar	8
2-5	Tow Bar Tube Design Curves	12, 13
6	Kevlar Sheath	17
7	Towing Lunnette	19
8	Lunette Eye	21
9	Lunette Clevis/Lugs	22
10	Sleeve	23
11	Lunette - Cross - Section	25
12, 13	Shear and Normal Stresses	26, 27
14, 15-32	Finite Element Models	30, 32-53
33	Loading Geometry	54
34	Cross - Section, Tube	56
35, 37	Eye	58, 60
36	Lunette	59
38-42	Clevis	63-67
43	Composite Tube Manufacturing Sequence	71
44	Sheath	73
45	Unidirectional Prepreg	74

LIST OF TABLES

TABLES	TITLE	PAGE
1	Unidirection Composite Material Static	
	Design Allowables	11

1.0 INTRODUCTION

Within the Tank-Automotive Command Research and Development Center's assigned mission is the responsibility for evaluating new materials and concepts which might relate to the Army's needs. The Lightweight Tow Bar Program evaluates the concept of a carry-along tow bar for battlefield recovery vehicles and the utilization of composite materials for vehicular applications.

Exxon Enterprises Materials Division (EEMD) was selected to develop the Lightweight Tow Bar (LTB) design through proposal competition. The LTB program will demonstrate the application of advanced organic composite materials on a current army inventory component, namely, the heavy duty tow bar.

Reducing the weight of battlefield equipment is viewed as necessary.

A lightweight tow bar will beenfit the Army in several ways. The LTB

will be less difficult to handle and install on a vehicle, hence fewer

personnel and less time will be needed when use of a tow bar is necessary.

The lightweight tow bar developed under this contract weighs 125 lb (56.7 Kg), as opposed to 340 lb (154 Kg) for the metal tow bar, thus meeting the program objective. The LTB is designed to be stowable on the M60 series and Abrams (MI) vehicles. Its basic configuration, installation, and function are identical with the currently inventoried steel tow bar (P/N 8383802). The legs, or tubes, of the LTB are fabricated from high strength graphite fiber-reinforced epoxy. These structural members are protected by an overwrap of Kevlar material. This arrangement yields a lightweight tube in which the structural component is shielded by a proven lightweight protection system.

Prior to actual prototype fabrication, a detailed analysis was made of all component parts of the tow bar, based on loads encountered under operational conditions. Next, material tests were performed on the composite components to verify their properties. Comparative tests were conducted on adhesives to determine the best system for bonding the metallic fittings to the composite tubes. Specimens of a preliminary joint design (which closely resembled the final design) were made and tested. These tests verified the design of the joint, while pointing out a need for a slight adjustment of the lay-up sequence of the original laminate.

A finite element model of the joint between the composite tube and the metallic fittings was constructed to verify the design. All of the analyses and tests were used to verify or adjust the final design.

These initial efforts lead to fabrication of a first LTB article to the final configuration. This first article was made with production materials, tools, and personnel. Fabrication of this tow bar was completed without problems, and was shipped to TACOM for testing.

Tests by TACOM personnel verified the design, and the go-ahead was given for prototype production. After fabrication, the composite tow bars were C-scanned, revealing well-developed laminates with no detectable internal flaws.

The metallic elements of the design were of high-strength alloy steel. Metal sleeves were adhesively bonded to the ends of the composite tubes. End fittings were subsequently welded to the sleeves by gasmetal arc welding (GMAW). After welding, the tow bars were painted forest green and were delivered to TACOM for further field vehicle testing.




FIGURE 1 - Composite Tow Bar

2.0 DESIGN DISCUSSION

The overall design of the tow bar was specified. Primary consideration of the design was to meet low weight requirements and towed vehicle to towing vehicle geometry requirements. The requirements which the prototype tow bars met are discussed in para 2.1 below. Sections 2.2 thru 2.3 discuss how the materials and the design configuration were chosen.

2.1 Design Criteria

- Material: The tow bar is to utilize composite materials in its design.

High strength graphite fiber reinforced epoxy was selected as the stress-bearing material. The stress-bearing members are provided with a Kevlar/epoxy protective overwrap.

- Weight: The weight of the tow bar shall not exceed 125 lb (56.7 kg).

The actual weights of the prototype tow bars, including all metallic fittings, were 124.3 and 124.5 lb.

- Stowability: The tow bar shall be stowable on the Abrams (M1) main battle tank.

Appendix A includes a drawing for the stowage of the tow bar on the M1 tank.

- Strength Requirements: The tow bar shall be capable of withstanding a 130,000 pound (578269 newton) load, in tension and compression, for a straight pull and push with a 180° angle between the vehicles with the tow bar in the deployed condition.

The tow bar analyses and tests to date indicate a capability exceeding the requirements given above.

- Dimensional Requirements: Similar in size - not to exceed the existing metallic tow bar dimensions.

The overall length from lunette eye to opposite eye of 83-1/2 inches for the composite and metallic tow bars is identical and the tow bars may be dimensionally interchangeable.

- Environment: The tow bar must be resistant to nominal damage or environmental degradation.

The Kevlar sheath which protects the high strength graphite/epoxy composite tube fulfills the environmental requirements.

2.2 Material Considerations

2.2.1 The Composite Tubes. The composite tubes used in the prototype tow bars are made from high strength graphite/epoxy, and have an external (outside) diameter of 4-1/4 inches. The properties of high strength graphite/epoxy, as well as other candidate materials, are shown in Table 1.

The weight versus diameter curves shown in Figures 2, 3, 4 and 5 best illustrate how the material was selected and how the optimum weight/diameter compromise was arrived at. Figure 3 illustrates the weight versus tube diameter (i.e., outside diameter) curves for high strength graphite/epoxy tubes with a length of 83-1/2 inches (2121 mm). For every value of tube diameter, there is a minimum weight of high strength graphite/epoxy material required for an 83-1/2 inch-long tube to meet the compressive strength, tensile strength, Euler (column) buckling strength, and cylindrical (wall) buckling strength requirements at the specified load conditions.*

*The tow bar is designed to transmit 130,000 lb (58968 kg, or 578269 newtons) in tension or compression. The geometry of the tow bar is such that each composite tube transmits 72631 lb (32945 kg, or 323079 newtons) under design load conditions. See Section 3.2.

	GRAPHITE/EPOXY		FIBERGLASS]
	HIGH STRENGTH	HIGH MODULUS	5-GLASS	E-GLASS	ARAMID .
LCNGITUDINAL MODULUS, MSI	18.0	24.0	7.1	5.4	11.0
TRANSVERSE MODÚLUS, MSI	1.5	1.1	1.4	1.2	0.8
SHEAR MODULUS MSI	0.60	0.65	0.55	0.65	0.3
POISSON RATIO	0.20	0.21	0.25	0.25	0.34
LONGITUDINAL STRENGTH, KSI TENSILE COMPRESSIVE	160.0 135.0	90.0 80.0	172.0 76.0	128.0 72.0	160.0 32.0
TRANSVERSE STRENGTH, KSI TENSILE COMPRESSIVE	6.4 13.5	3.2 16.0	7.0 20.8	2.5 16.0	3.4 16.0
SHEAR STRENGTH, KSI	8.0	6.0	5.6	<u>-</u> 5.6	7.0
DENSITY, Lb/in ³	0.06	0.06	0.073	0.073	0.05

TABLE 1 — Typical Unidirectional Composite
Material Static Design Allowables




FIGURE 2 — Tow Bar Tube Design Curves - High Modulus Graphite/Epoxy




FIGURE 3 — Tow Bar Tube Design Curves - High Strength Graphite/Epoxy




FIGURE 4 — Tow Bar Tube Design Curves - E-Type Fiberglass/Epoxy




FIGURE 5 — Tow Bar Tube Design Curves - Aramid/Epoxy

From a study of the four minimum weight versus tube diameter, curves shown in Figure 3, it can be shown that a diameter somewhat greater than 5 inches (127 mm) can meet all four criteria with a lower weight of material than tubes of the same material with lesser or greater diameters. However, a tube with this diameter would be difficult to handle and, in addition, would be more susceptible to accidental damage than a tube that is smaller in diameter. Therefore, 4-1/4 inches (108 mm) was chosen as the most suitable diameter. A high strength graphite/epoxy tube so designed weighs about 8 lb (3.63 kg), which is more than the weight of a tube of the same material at the optimum diameter. However, if enough material is used to meet the Euler buckling criteria, the tube will exceed the minimum requirements regarding compressive strength, tensile strength, and cylindrical buckling strength.

Figures 2, 4, and 5 are minimum weight versus tube diameter plots for high modulus graphite/epoxy, E-type fiberglass/epoxy, and Aramid fiber/epoxy, respectively. As with Figure 3, each of these figures shows four curves representing, for each value of tube diameter, the minimum weight of the given material required for an 83-1/2 inch-long tube to meet the four aforementioned strength criteria when subjected to the design load. Note that for high modulus graphite/epoxy, a 4-1/4 inch diameter tube using somewhat more than 6 lb (2.72 kg) of material will meet all four strength criteria with compressive strength being the critical factor, as opposed to Euler buckling for high strength graphite/epoxy.

With E-type fiberglass/epoxy or Aramid fiber/epoxy, it would take over 12 lb (5.44 kg) of material for an 83-1/2 inch-long tube to meet the compressive strength criterion.

With E-type fiberglass/epoxy, an 83-1/2 inch-long tube would have to have a diameter of six inches (152 mm) to marginally meet the Euler buckling criteria at the minimum weight required to meet the tensile and compressive strength criteria. For Aramid/epoxy, a tube 4-1/2 inches in diameter requires approximately 13 lb (5.9 kg) of material to meet the compressive strength criteria.

Accordingly, graphite fiber reinforced epoxy, using either high strength

or high modulus fibers, constitutes a more weight-effective material than E-type fiberglass/epoxy or Aramid/epoxy. Graphite fiber reinforced epoxy is also more cost-effective than the aforementioned alternatives.

2.2.2 The Metal Fittings. The metallic parts are high strength 4140 alloy, weldable, military specification steel. Since more than 85% of the weight of the prototype tow bar is in the metallic fittings, a good design effort was necessary to minimize their weight contribution. Metal was removed wherever possible. However, a fitting factor of 1.2 was used in the design calculations to assure a safe design.

2.2.3 Adhesive Material Selection. A number of adhesives were considered for use in the tube-to-metal joint. Comparative tests were performed on these adhesive materials, which resulted in the choice being narrowed to two candidates. Because the adherends being joined are dissimilar materials, both adhesives were used, as will be discussed later.

2.3 Tow Bar Design

2.3.1 Composite Tube Design. The tube was sized for least weight, given the constraints of strength requirements, handability (i.e., ease with which the tube can be grasped by the average soldier), and damage resistance. An outside diameter of 4-1/4 inches was chosen as an acceptable compromise between the lesser weight of a larger diameter tube and

the need for the tube to be amenable to handling with a thumb-opposed grasp. Also, damage resistance is a function of thickness to diameter ratio, accordingly, the smaller diameter tube was felt to be less susceptible to damage.

The ply orientation is ±45°/0°/±45°. This orientation gives the tube the axial stiffness required for buckling resistance, yet yields a laminate with good overall strength and integrity. A preliminary choice of laminate orientation with some 45° plies at the mid-plane proved to have some processing difficulties and was discarded. The final laminate configuration showed no trace of the earlier problems, and was shown to be a good choice during tests. Wall thickness of the laminate was 0.21 inches (5.33 mm).

A Kevlar overwrap, consisting of four plies of woven fabric, was wrapped around the graphite/epoxy tubes. The sheath serves a dual purpose. Its primary purpose is to protect the graphite fiber laminate. Kevlar is highly resistant to abrasion and, in addition, can absorb considerable amounts of impact energy. Hence, the Kevlar overwrap offers protection to the underlying stress-bearing materials against scratches, nicks, etc., which would otherwise occur during service and which could jeopardize the tow bar's structural integrity. Sufficient Kevlar was used to allow for expected abuse of the tow bar while still being consistent with the 125 lb (56.7 kg) weight limitation.

The secondary function of the Kevlar overwrap is to serve as a mandrel during the fabrication process. First, the overwrap is formed on a male mandrel, cured, and trimmed to the proper size. Figure 6 illustrates a finished overwrap. The Kevlar overwrap is then used as an external mandrel, against whose interior the graphite/epoxy composite tube is formed.



FIGURE 6 - Finished Kevlar Sheath

2.3.2 Design of the Metal Parts. There are two types of metal parts used with the tow bar: the fittings which act as lugs, and the sleeves which are adhesively joined to the ends of the composite tubes.

The fittings include the lunette, the eyes, and the clevises.

Typically, the worst problem with lug-type fittings is to make sure the transition area between the lug and the other end transfers the load adequately.

The lunette is the heaviest single part of the tow bar. Its function is to transfer the maximum expected load, in either tension or compression, from the towing vehicle to the two composite tubes, which in turn transfer the load, via metal fittings, to the towed vehicle. Figure 7 shows the lunette.

The large eye is the pintle attach point for the towing vehicle.

The lunette divides the towing force, with 1/2 of the force directed onto the integral shaft and the other 1/2 of the force onto the deployable shaft which attches and pivots at the set of lugs with the smaller eye.

The lunette, therefore, has both mechanical joints and a weld joint. Design calculations must be based on the strength properties of the steel alloy in the as-welded condition when dealing with metal at or near the weld. In other areas, the lunette is heat treated to strengths of 180,000 to 200,000 PSI $(1.24 \times 10^3 \text{ to } 1.38 \times 10^3 \text{ MPa})$ ultimate tensile strength. This heat treatment makes it possible to reduce section thickness and thus reduce weight, via improved strength.




FIGURE 7 — Towing Lunette

Design of the eye shown in Figure 8 is more straightforward. At one end is a lug which serves as a mechanical joint. At the other end is a tube section which is welded to a metal sleeve, which in turn is adhesively bonded to one of the two composite tubes. A transition section is provided between the lug and the tube section. Like the lunette, the eye is heat treated at the lug end, to allow reduced section thickness and hence reduced weight.

The clevis (shown installed on the tow bar in Figure 9) is a double set of lugs at 90° to one another. The design problem with this part is to allow sufficient load transition area while reducing weight to a minimum. Because there are no welds, it is fully heat treated to 180,000 to 200,000 PSI tensile strength. The design is based on straightforward lug analysis, except that with one set of lugs there is a bending moment to consider, due to the geometry.

The sleeve (Figure 10) serves as a transition piece between the metallic components and the composite tubes. One end is welded to the lug fittings, which may be either an eye or the lunette. The opposite end is tapered, and is used to form an adhesive joint with an end of one of the composite tubes. The design of the sleeve-to-composite tube joint is discussed in the next pargraph.




FIGURE 8 — Lunette Eye




FIGURE 9 — Lunette Clevis/Lugs





FIGURE 10 - Sleeve


2.3.3 Adhesive Joint Design. The primary problem of any joint is to smoothly transfer the load from one element to another. A composite-to-metal joint offers the additional problem of highly dissimilar properties which affect the joint loading rate. The joint design, then, must consider how to reduce the stress concentrations and peaking induced by this imbalance of properties. A mechanical joint using fasteners, while necessary in some conditions, is generally limited in composites due to the low bearing strengths of composite materials. In the design of the tow bar, an adhesive joint (shown in Figure 11) was considered to be the best solution.

In any adhesively bonded joint, there are shear stress peaks near the ends of the joint, due to shear lag. Figure 12 illustrates this for a double lap joint. A single scarf joint will reduce these end concentrations as Figure 13 illustrates.

As stated in the Advanced Composites Design Guide*, a unique characteristic of scarf joints is that bond shear strength can be increased indefinitely by increasing the length. Also, as the length of the joint is increased, the ratio of average shear stress to peak shear stress decreases asymptotically to a limiting value, which is equal to the lesser ratio of the extensional stiffness of the adherends. Thus, by maintaining a constant value for the modulus of each adherend times its thickness, the peak shear stress in the adhesive at the ends of the joint can be minimized.

^{*}Volume II (Analysis), Third Edition, Third Revision, Paragraph 2.4.1.5.7.3








FIGURE 12 - Adhesive Shear and Normal Stresses in Composite Double-Lap Joint




FIGURE 13 - Maximum Shear Stress in Scarf Adhesive Layer

This is accomplished by the joint configuration adopted for the tow bar. The modulus of the composite ply lay-up is approximately one-half that of steel, while the thickness of the steel sleeve is roughly one-half of the thickness required for the composite to meet the local buckling stength criteria. Thus the ratio of the extensional stiffness of the steel and composite sections at the joint is approximately unity. This results in a peak shear stress in the adhesive which, in theory, is not much more than the average shear stress.

A finite element model and analysis were made of the steel-to-composite joint to attempt to verify the design. This analysis is shown in the following section. Variations on the design were tried in an attempt to lower the peak stresses which occurred at the ends of the joint. These models demonstrated several points of interest in joint design:

- a. A tapered joint does reduce the peak stresses at the ends of the joint, but changes in the slope or even the location of the taper do not affect the end peak stresses appreciably. The stresses in the interior are affected, but these stresses are generally less than 1/2 of the beginning peak stresses.
- b. Holes in the adherends or holes in the adhesive (which might represent unbonded areas) have no real affect on the joint as long as they do not occur at the end of the joint. This shows that as long as care is taken at the joint ends, the joint is rather forgiving of manufacturing errors.
- c. Use of adhesives with different stiffnesses has an approximately 10% effect on the peak stress. By using an adhesive with lower stiffness

at the ends of the joint, and an adhesive with higher stiffness in the central portion of the bonded area, the shear stresses at the ends can be reduced.

The bond shear strength was conservatively assumed to be 1000 PSI (6.895 MPa) when carrying out the design calculations. According to vendor-supplied data, a lap joint specimen was tested at an average bond shear stress of 3500 PSI (24.13 MPa).

Proximity of the adhesive joint to a weld could result in degradation of the adhesive, but precautions during welding were taken to minimize heat build-up and promote heat dissipation away from the joint. During the test made by TACOM on the "first article" tube, a weld was made in the same area where the design weld would be placed. There was no apparent detriment to the adhesive joint's ability to bear the required load.

3.0 ANALYSIS

Analysis must proceed with a design in order to have a base on which to build. Part of this section discusses the early analysis done in order to design the composite-to-metal sleeve joint correctly. This finite element analysis is discussed first. Then, an analysis of the final design, component-by-component, is presented as proof of the design.

3.1 Finite Element Analysis of the Adhesive Joint

A finite element model was made to simulate the adhesive tapered lap shear joint of the composite tube to the metallic sleeve. The model is shown in Figure 14.

The purpose of the model was to analytically check the stresses and the distribution of stresses which occur in the bond line between the metal and composite adherends.




FIGURE 14 - TACOM Finite Element (F.E.) Model of Tow Bar Adhesive Joint

The double-tapered lap joint for the lightweight composite tow bar was modeled using the CQUAD2 element of NASTRAN level 17.5. This model contained 556 elements and was of a two-dimensional configuration. To ease input data generation, the model was made in a rectangle configuration and elements located where no material existed were given material properties approaching zero. The zero property elements are marked with '0' in Figure 14 and the elements representing the adhesive are marked with an 'A'. The model, in all other aspects, matched the geometry of the joint exactly. Various changes in the geometry, such as taper ratio and adhesive line placement, as well as different types and combinations of adhesives, were explored A total of seven separate computer model runs were made.

NASTRAN's CQUAD2 element is a quadrilateral plate element with both in-plane and bending stiffnesses that assume a solid homogeneous cross-section. The material properties of a given element can be modeled as linear, temperature-independent, and isotropic; or linear, temperature-dependent, and anisotropic. In our model, we used both types of material data input to model the steel, adhesive, and composite appropriately.

Run No. 1 (performed on the model shown in Figure 15) was carried out to establish a data base for comparison with the results of subsequent runs. In this way, the relative merits of the various configurations could be judged. The initial model has adhesive properties identical to those of the resin used in the laminate. The results of that run are plotted in Figure 16.

The abscissa is the distance along the joint length from all metal at the origin to all composite at the extreme right.

Comparing the model to the graph, it can be seen that there are three peak stress locations: at the tip of the composite material, at the beginning of the taper in the metal and at the tip of the metal. These peak stresses are associated with shear lag in the joint.

A lap joint without a taper is characterized by a shear stress distribution with peaks only at the corners. The area in the middle of the joint is ineffective and as can be seen from Figure 17, the shear stress in the middle is many times smaller than the peak tip stresses.

As a comparison of Figures 16 and 17 indicates, the tow bar joint design geometry increases the effectivity of the center portion of the joint and thereby decreases the tip peaking.

Figures 18 and 19 show the same geometry as Figures 15 and 16, but now the adhesive is modeled as having the properties of Narmco Metal Bond 1113 adhesive. The curves, as might be expected, are very similar. The maximum peak stress was reduced, however, due to the reduced stiffness of the adhesive from 3,500 PSI to 3,200 PSI (24.13 to 22.06 MPa), or approximately 9%.

From the results of Figure 17, compared to Figure 19, it might be predicted that a "stiff" adhesive used in the middle of the joint and a "soft" adhesive used at the tips might cause a transfer of load to the middle section of the joint, away from the regions of peak stress. The model affirmed this. Using a softer adhesive for the first and last inch of the joint reduced the stresses at the tip. A small peak formed at the glue transition line. Figures 20 and 21 illustrate the case of a joint using both "stiff" and "soft" adhesives.

Analysis of peak stresses reveals a reduction from 3,200 PSI for the "all stiff" adhesive to 3,000 PSI (22.06 to 20.68 MPa), a reduction of about six percent.

Model No. 4 looked at the problem of a 'hole' in the glue. A one-inch length of the glue line was given zero properties to simulate a hole. Figures 22 and 23 show this hole and the resulting shear stresses. Almost no effects are felt at the tips and 'mini-peaks' occur at the hole edge. These results indicate that the joint is very forgiving of processing errors or omissions in the center of the joint. Tips of the joint, however, must be carefully made.

Model No. 5 investigated the possibility of utilizing a double taper. The basic concept was to induce shear stress peaks in the central region, and hence reduce the magnitude of the peaks at the ends of the joint. By using two slope transitions, it was hoped that the peak normally occurring in the middle of the joint (at the junction between the flat and sloped areas) could be made to occur twice. Figure 24 illustrates the model. The results, shown in Figure 25, reveal that the two peaks do occur as per the original concept, but the peak stresses are not reduced.

Model No. 6, shown in Figure 26, investigates the effects of changing the slope of the bond line. It was theorized that by increasing the length of the slope, the shear stresses at the ends of the joint would be reduced. The results of the computer run, shown in Figure 27, confirm that a reduction in shear stress at the joint ends does occur, but only to a limited extent - from 3,000 PSI to 2,800 PSI (20.68 to 19.31 MPa), or 7%.

Another configuration subjected to computer evaluation involves reducing the extensional stiffness of the metal sleeve by drilling three rows of holes. In the model shown in Figure 28, properties are lowered to simulate metal removal. The results, shown in Figure 29, reveal that peak stresses are increased, not decreased, by 200 PSI (1.379 MPa) relative to the base configuration.

Model No. 6 was the adhesive joint configuration finally adopted. As noted above, a peak shear stress of 2800 PSI was determined by computer calculations for this arrangement.

In order to judge if the results from these models are valid, computer modeling of the standard lap-type shear test specimen was carried out, assuming both AF 13 (manufactured by 3M) and Metalbond 1113 (Narmco) adhesives. The results of these runs were compared with laboratory test data. In general, test results are given in terms of "averaged" stresses (i.e., load divided by area). It is known that peak stress far exceeds this number and the middle stresses are far below it. Laboratory tests have shown that a smeared or average shear stress reported by testing or by a vendor of 3,000 PSI; e.g., either AF 13 or Narmco 1113 adhesive, corresponds to about 3,500 PSI (See Section 5). The model of the one-inch square bond area test specimen is shown in Figure 30 and the results in Figure 31 are for the Narmco Metalbond 1113. The results for AF 13 are shown in Figure 32.

In both cases, the peak stresses are roughly 3-1/2 times the average stress. This says that a test specimen which fails at an averaged stress of 3,000 PSI is experiencing a peak stress of 10,000 PSI 869.95 MPa) or more.

Since the peak stresses of the models are only 2,800 PSI, the joint may be viewed as very conservative.

It may be noted, however, that the average stress for the joint is about 1,000 PSI. This says the peak stress is 2.8 times the average. Thus, with all that was accomplished, using both geometry and material properties, peak stresses were reduced 25% from a step lap joint.

							٥	0	• •	9	٥	ءاء	ءاد	de	0	b	0	0	o	6																										
							0	٥	0	٥	0		۰	9 4	0	, 0	0								\mathbb{L}																					
							0	0	٥	, ,	٥	٥	,]0	0	7		Γ	Γ		-					Τ		П		1		П					T	T	Ī				T				
		Ī	···				0	0	0	9	9	•	1	T	Ī	7	Γ	Γ					7	7	Τ		П	7	T	Γ	П					Ţ	T	Ī	\Box			7			7	
_	-	•	34-4				٥	P	0	1	T	7	7	7	1	1	Γ	Γ	П		П		7	1	1		П		T		П			7	1	1	T	Τ				7	•		T	
								П	7	1	1	T	7	T	1	1	Γ	Γ					7	7	1	Γ		T	7	Γ			٦	1	7	7	1	1				7			7	 -
								1	- 1																									- 1	1			1		• 1						
							1147	1101	2					12	13	12:2	1500	1952	102	150	27.2	12.	5	1	┪	-	+	┪	†	-	Н	+	1	+	1	\dagger	\dagger	\dagger	1		-	†		_	+	-
7	- T	- [- Ţ	_		 <u> </u>	1111	161	2 3	12.2				1532	5002	12.2	5000	1112	4102	1500	2102	111/11/11			777.7	107		+	1					1	1	†	†					†			-	
1					•	 	fint	le!	77.	1000	1			1733	(1)	12.2	5005	192	101	1501	2103	111 fre/		17.17.	27.1 1.112	Petr Post	123	100	10.1	1.67						† -										_
							fint	les !						172	- CE	10.2	(1)2.	192	4102	16.07	2103	111 fre/			27.1 1.6.5	1011 1051	123	100 Car	10.1	1111 1111	1101	1,4,1			1	+										
							FIAT	the			1000			172	100	129	5000	77.2	41.2	160	2002	Part Fert			29.11.60	Petr Por	155	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	10.11	1111 1111	1103				<i>b</i> , 1		1									_

FIGURE 15 - Run #1, TACOM F.E. Model of Reference Tow Bar Adhesive Joint





FIGURE 16 - TACOM F.E. #1 Glue Shear X-Y (Resin Glue)






FIGURE 17 - Adhesive Shear and Normal Stresses In Composite Double-Lap Joint

1	1	• ,	•••				0	0000	0	0	00		0	0	-	-1	0		5																									
	•	`	314		•		o		-		-		200	25.	1	500			1	1 1 1/13	1 2.40									1														
								7	-		1			_						4 400	1.20.1			<u>に</u> に	[]	12.		1		1	1	-			1			F	1					
. }		 			_	7		+	-		1	1	 -			1	+	+	-			1		1					1111				1	111	+			F	1					
				- ,.	<u> </u>	1		士			上					1	1	上				<u> </u>	<u> </u>	_		1	1			1	Ï	L	_			0	۵	0	1	0	0	0	0	ح ا

FIGURE 18 - Run #2, TACOM F.E. Model of Reference Tow Bar Adhesive Joint Using Narmco Metalbond 1133 Adhesive




FIGURE 19 - TACOM F.E. #2 Glue Shear X-Y (1133 Glue)

									0	0	0	0	o	0	0	0	0	0		9	0													I				L							I	
									0	0	0	0	0	0	٥	0	0	9 6	9					<u> </u>							Ц					Ц								<u> </u>	_	
									0	0	0	0	0	0	0	0								1			Ц		1		Ц	\downarrow	_			Ц	1		1				<u> </u>	Ļ	\perp	
17	<u> </u>	_		••••		_			o	٥	0	o K	0							_		Ц	_ .		\perp			\perp			Ц	1	_	1	L		1	_	1				<u> </u>	<u> </u>	1	
İ		-	•	/. 55 41	•	•			0	٥	0							_ _	_	_			4	_	_	_	Ц	_ .	1	_	Ц	1	_	_	\perp	Ц	-	_	4				_	<u> </u>	1	
- !															Ц					1					1	_		4	1	_	Ц	1	1	1	L	Ц	4	↓	4			_	 	╀_	+	
										1	7. 5.			12	1	3	3			3	É	3				L	Ц	_	1	_	Ц	\downarrow	_ _	_	L	Ц	4	$oldsymbol{ol{ol{ol}}}}}}}}}}}}}}}}$	4				1_	╀-	ļ	
										1																:		1	1		Ц	1	1	1		Ц	丄	Ļ	4				1	<u> </u>	1	
							T	T		1	П	7	7	Т	П											٤	3	20.		1					<u> </u>	Ц	\perp						<u> </u>		1	
		<u> </u>						Ī	\top	1	П	7	7	T	П														1		12	3													_	
f								T		1	П	7	7	T	П		٦		T	7	1	П													1	3									_	
·							T	T	1	T	П	1	1	T						\prod												$oldsymbol{\mathbb{L}}$	1			\coprod	٤١٤]_e	<u>.</u>	0	0	0	0	0		0

FIGURE 20 - Run #3, TACOM F.E. Model of Tow Bar Adhesive Joint Using "stiff" and "soft" Adhesives




FIGURE 21 - TACOM F.E. #3 Glue Shear X-Y (AF-13 and 1113 Glue)

	000000	0000000	001111			
	00000	 - - - - - - - - - -			 	
		000				
J. J	000000					
)(44E	000					
	752		(30)			
			1,300	131		
				10000		
				130 00 00 00 00 00 00 00 00 00 00 00 00 0	1103	
	<u> </u>		<u> </u>	720) 120 120) 120 120) 120 120) 120 120) 120 120) 120 120)		
					11:00	00000

FIGURE 22 - Run #4, TACOM F.E. Model of Tow Bar Adhesive Joint in Which a "hole" is Simulated




FIGURE 23 - TACOM F.E. #4 Glue Shear X-Y
(AF 13 1113 Glue w/Hole)

							٢	_	T	Т	T.	Τ.	T	Γ		٦			٦			7	٦	T	Т	Т	Т	Т	T		Т	Т	Т	Τ	Т	П		1	1		Т	1		T	T	7		_	Т	<u></u>
								인	0	٥١٩	2	2	9		d	0	9	9	9	9	9		┚	_1	_].			1_	1_				L	1_					\perp		1_	_[<u>L</u>		-		<u> </u>		
							[0	اد	9	9		0	0	0	0	Ó	0																											1				T	
	•	•					- 1		2	0	9	0	0	0	0										1				Γ			T												Π	Τ	1			T	
•		0.03	•				- 1	0	0	2 0	2	7		Γ		٦		7	7					7	1	7	T	Τ	Γ		T	T	7	Γ				1	T			1			T	7			T	
		30	/, 00°	-		-			of	9	T	T	Ι.	Γ	П		٦			٦	٦	7			7		Ī	7	Γ		T	T	T	Γ		Ī		1	1		Γ	7		Γ	T	1			1	
										T	T	T	Γ	Γ			7		7		٦					1	1	1	Τ		T	T	Ī	Γ		Ī		1	1		Γ				T	Ī			T	\neg
							Ī	2			1	7.9.2	is:	25.3	3.2					٦					-	1		1			7	7	T				7	7	7		Γ	1			1	7			Τ.	
				T	T			1	1	Ī	T	T			2.63	٤		7/2		٦	٦	7		7	1		T	Γ			1	T	T				1	1	1		Γ	1				1			1	٦
-				Ī	7				7	T	T	Τ					7			3	3	2.	Ž.	3	2		13.0	13.	1	1.1.6	200		T			7	1	1	1			1				1			1	٦
					Ī			T	T	T	Ī								1			T	7	T	T	T	T	Ī			2		5	25.5	3	٦	1	7	Ī		Γ	1				7			1	٦
					Î	 Γ		1	T	7.	T	T	Γ				7	7	1			7	7	7	- -	1	T	Γ			T	Ī	7	12.2	1	2				0		T				T			1	٦
	Ì	Ī		1	Ť			7	7	T	T	Γ				1	T	1	7	٦	7	7	1	T	7	T	7		П	٦	T	T	Γ	П	П	Ī				0	7	5	0	0	,	寸	0	0	-	7

FIGURE 24 - Run #5, TACOM F.E. Model of Tow Bar Joint in Which Two Slope Transitions are Simulated




FIGURE 25 - TACOM F.E. #5 Glue Shear X-Y
(AF 13, 1113 Glue + Diff. Glue Line)

	***	•.		0.03"	; 00°				6			0 0 0 0	10 0 01	0 0	0	0	200	2	6	0	9		7-	1-		7	0,9	00	ro																
. *		.		Γ		T		1	1257	1	1.00	(6.3)	76-3	29:3			1:1:	5 4.2	613	23.2	· · · · · · · · · · · · · · · · · · ·		1/4/1	26.1 200	1.51						† †	† 	 	1	<u>†</u> 				1					_	
			1	 			1		- -	-	1			1	<u> </u>	-					1	1	12	٤					3111				1	1	†				1	1					_
	-	+	1	 		+	+	 <u> </u>	+	-	+	-		1	$\frac{1}{1}$	+	-	-		1	-	$\frac{1}{1}$	-			-	+	1		118			7763		1 12	165		_	-	+	-				_
]_				\prod			I	\mathbb{L}	I				T	\mathbb{I}						I				I		I			I	I	I			1	0	0	1	0	0	0	0	0	0

FIGURE 26 - Run #6, TACOM F.E. Model of Tow Bar Joint with Lengthened Slope




FIGURE 27 - TACOM F.E. #6 Glue Shear X-Y
(Run #3 & Larger Slope on Comp.)

	000000000000000000000000000000000000000	
	000000000000000000000000000000000000000	
•	00000000	
17	000000	
7.00° 2646	000	
		1
		
		00
J J J J J J		

FIGURE 28 - Run #7, TACOM F.E. Model of Joint with Holes in Metal Sleeve




FIGURE 29 - TACOM F.E. #7 Glue Shear X-Y
(Run #3 & 3/4 Steel in Three Rows)

Lap Joint Test 600 Element -Glue Section- (AF13) Shear Stress X-Y

ŧ	4.50	TF.		13		Te	
1			7313		9113 9013	'n	9.50
	4413	4	4013				74.7
E E	8.013		8.013	15.		ic.	8013
-	7.213		7.213	15	7,13	14	2,2,9
1	1.413	12	6413	12	69,3	15.	. 693
1	57.3		5913	15	5.7,3	15	57.1
E	5.113		5/+3	1	5.1+3	5	5/13
E	4.6+3		4673		4.6+3	<u>Ę,</u>	4613
3	4.113	3	4.1+3	13	4.143	3	4113
370 177	3.743		37r3	13	3713	×	3.7+3
310	3.313	no.	3.3r3	310	3.3+3	2.0	32.3
2	3.0+3	63	3.0+3	1.	30+3	14.	3013
2	2.7+3	15	2.7+3	Ę	2 9.3	2	2.7-3
2	2.4-3	15	2413	4	2++ د	24.2	24+3
	ومدبر	13	22+3	ž	ي د د	*	23.3
311	2013	Į Š	2013	1	7405	\$	2013
2	1.9/3	5		È	1813	-	
2		3	1.7+3	1	7,973	3	/.113
	1613	13	1.673	<u></u>	16.3	<u>5</u>	16+3
1,43	19+3	-	1.9r3	3	- 19+31	<u> </u>	1.7.3
1	1.6+3	10	1.6+3	1	14.3	\$_	1.6+3
310	1.5+3	13	1.5+3	=	<u> </u>	<u> </u>	16-3
133	1.4+3		1.5+3	57	15,3	<u> </u>	1543
105	1.4+3		1.413	111	14.3	5_	<i>15</i> -3
13	1.3+3	18	1413		14.3	<u> </u>	140
22	1.413	Z	1.3+3	Š	1.3+3	<u>5</u> _	· <u>133</u>
354 955	1.1+3	12	1./+3	27.5	143	<u> </u>	1.143
5	1.3+3	3.1	1.2+3	37	الجرور	<u> </u>	12.3
S	1.3+3	3	1.3+3	2.5	· 1.3+3	E.	1.3+3
32	1.3+3	3	1.3+3	5	1.313	3	1.303
25	1.4+3	3	14.3	7	1413	<u> </u>	14,5
<u>&</u>	1.4.3	13	1.413	5	1.4+3	•	1.7-3
E	1500	\$	1.5-3	-	157	5	153
Ę	16+3	3	1617	<u> </u>	11.7	5	14.5
E	1813	2	1.2+3	.	اوبور	5	1.5+3
2	1.9+3	3.6	1.913	}	1.9.3	`	19+3
	2.1+3	305		<u>5</u>	ادرو	<u>5</u>	2.43
364 378	2:3+3	304	23.3	} _	23-7	<u> </u>	2.3+3
Ė	2613	3.5		<u> </u>	اوبحد		
145 541	2.9+3	5		<u> </u>	25.21 2.818.C		25+3
12.	2.7-3	<u> </u>		<u>-</u>	29.3	<u>. </u>	20+3
<u> </u>	F./*3	`	Z.**, 3	<u> </u>	27531		

FIGURE 30




FIGURE 31 - Area Under Curve #1 = 2990.125 psi/in




FIGURE 32 - Area Under Curve #1 = 3007.500 psi/in

3.2 Tow Bar Analysis By Component

The tow bar is the connective element between a towing and a towed vehicle. The design conditions are based on a vehicle gross weight of 120,000 lbs. and a coefficient of friction which does not exceed unity. A margin of 10,000 lbs. was added due to uncertainty of actual vehicle gross weights.

The assumed geometry for this 130,000 lb. load is for a straight pull at a 180° angle between vehicles. No allowance for a differential increase in load in one tube or the other of the tow bar, due to a pulling angle different than a straight pull/push, was considered.




FIGURE 33

As can be seen from the geometry, it is assumed that each leg of the tow bar will take one-half of the 130,000 lb. load or 65,000 lbs. in the direction of vehicle alinement. This works out to a 72,631 lb. (323079 newton) load on each tube in its individual axial direction, after consideration of the 53° included angle between tubes.

3.2.1 Composite Tube Analysis

The composite tube will be considered first. The loads, just given, are a simple condition of axial tension or compression equal to 72,631 lbs.

The tube geometry is:

OD = outside diameter = 4.25 in.

ID = inside diameter = 3.81 in.

I = moment of inertia = $\mathcal{T}(0D^4 - ID^4)$ = 5.671 in.⁴

 $A = area = 2.785 in.^{2}$

L = length = 83-1/2 in. (pin to pin)

 $E = modulus = 13.46 Psi \times 10^6$

First consideration is tube stability. Assuming the tube to be pin ended, the critical load Pcrit is given by:

Perit =
$$\frac{\pi^2 \text{ EI}}{\text{L}^2}$$

Perit =
$$\pi^2$$
 (13.46 x 10⁶) (5.671) (83-1/2)²

Pcrit = 108059.2 lbs.

MS = margin of safety =
$$\frac{108059.2}{72631}$$
 -1 = 49%

Now, considering tube strength, the ultimate compressive stress, Fcu, for this tube is 101,000 Psi. The ultimate compressive load, Pcu, is given by:

Pcu = FcuA


 $Pcu = 101,000 \times 2.785$

Pcu = 281319 lbs.

$$MS = 281,319 -1 = 158$$

NOTE: 1.5 is the factor of safety

The joint between the composite tube and the metallic end fittings is bridged with a tapered metal sleeve. It is bonded integrally to the tube. This joint is the next consideration.



The bond length of this single srcaf tapered joint is 8.75 inches.

The average diameter of the bonded surface is:

Dia.
$$\frac{4.21 + 4.01}{2}$$
 = 4.11 inches

Therefore, the total available bond area is:

Aadh = (
$$\pi$$
) (Dia) Length
= (η) (4.11) 8.75
= 112.98 in.²

Adhesive strength is given by the manufacturer as 2,500 Psi but because of length of the bond and manufacturing uncertainties, a bond strength of 1.000 Psi ultimate shear strength is assumed. Thus, the calculated joint strength is:

Padh = Fu, adhesive x Area

 $P_{adh} = (1000) (112.98)$

 $P_{adh} = 112979.52 lbs.$

 $MS = \frac{112979.52}{(1.5)(72631)} -1 = 3.7$

3.2.2 Steel Sleeve

This sleeve, as mentioned, is the bridge between the metallic fittings and the composite tube.

OD = 4.25 in.

ID (Midbody) = 4.00 in.

 $A = 1.6198 \text{ in.}^2 \text{ (Midbody)}$

Material = 4130 Cold Rolled Steel in 'N' Condition

Fcu (ultimate compressive strength) = 90,000 Psi

Checking the strength we get:

Psleeve = FcuA

= (90,000) (1.6199)

= 145789 lbs.

MS =
$$\frac{145789}{(1.5)(72631)}$$
 -1 = 33.8%

3.3.3 Weld Joint

The steel sleeve is welded to metallic end fittings (lunette or eye). The alloy steel is assumed to have an ultimated tensile strength, $^{\rm F}$ tu, of 51,000 Psi in the weld zone as given by MIL I/BK 5 for a Class 1 welding rod.

OD of weld - 4.25 in.

ID - 3.89 in.

This joint has an area of:

$$_{\text{Weld}}^{\text{P}} = \frac{\mathcal{T}(\text{OD}^2 - \text{ID}^2)}{4} = 2.3015 \text{ in.}^2$$

 $P_{\text{Weld}} = (2.3015) (51000)$

= 117378 lbs.

$$MS = \frac{117378}{(1.5)(72631)} = 7.78$$

3.3.4 Eye Fitting

This fitting is simply a lug.

Lug Thickness = 1.44 in.

Material = 4140

Ftu (ultimate tensile strength) = 125,000 Psi

 F_{su} (ultimate shear strength) = 75,000 Psi

Fbu (ultimate bearing strength) = 151,000 Psi

First Checking Tension in the Net Section:

Area = $(3.0 - 1.25) 1.44 = 2.52 in.^2$

 $P_{ten} = F_{tu \times A}$

= (125,000) (2.52)

= (315,000 lbs.

MS = $\frac{315000}{(1.5)(72631)(2)}$ -1 = $\frac{141\%}{(1000)}$ (includes fitting factor of 1.2)

Next Checking Shear Tearout:




FIGURE 35

Area =
$$(.966)$$
 (1.44) (2) = 2.783

$$P_{Shear} = F_{su}A$$

= (75,000) (2.783)

= 208,742 lbs.

MS =
$$\frac{208742}{(1.5 (1.2) (72631)}$$
 -1 = 60% (includes fitting factor of 1.2)

Checking Bearing:

Area =
$$(1.24) \times 1.44 = 1.785$$
 in.

$$P_{Bear} = P_{Bu}A$$

= (151,000) 1.785 in.

= 269625 lbs.

MS =
$$\frac{269625}{(1.5)(1.2)(72631)}$$
 -1 = 106%

3.3.5 Lunette

The lunette provides the confluence point for the tow bar legs and the forward attachment point for the towing vehicle.




FIGURE 36

Checking the Clevis End of the Lunette:

Material - 4140

Ultimate Tensile Strength - 180,000 - 200,000 Psi

Ultimate Shear Strength - 108,000 Psi

Ultimate Bearing Strength - 250,000 Psi

Lug Thickness - 0.60 in.

First Checking for Tension Across Net Section:

Area = $(3.00 - 1.25) (0.60) (2) = 2.10 in.^2$

 $P_{tension} = F_{tu}A$

= (180,000) (2.1)

= 378,000

 $MS = \frac{378,000}{(1.5)(1.2)(72631)} -1 = 189$ %

Next Checking Shear Tearout:




FIGURE 37

Area =
$$0.966 \times 1.20 \times 2 = 2.32 \text{ in.}^2$$

$$P_{Shear} = F_{su}A$$

$$=$$
 (108,000) (2.32)

$$MS = \frac{226,800}{(1.5)(1.2)(72631)} = 928$$

Checking Bearing:

Area =
$$(1.25) \times 1.20$$

$$= 1.50 in.^2$$

$$F_{BU} = 250,000 Psi$$

$$P_B = F_{Bu}A$$

$$=$$
 (250,000) (1.50)

$$=$$
 375,000 lbs.

$$MS = \frac{375,000}{(1.5)(1.2)(72631)} -1 = 1878$$

Next Part of the Lunette to be Analyzed will be the 'Big' Eye:

Checking the Net Section in Tension:

Area =
$$2 [\pi (1.625^2 - 0.625^2)] = 3.534 in.^2$$

$$P_t = F_{tu}A$$

$$=$$
 (180,000) (3.534)

$$MS = \frac{636,172.5}{(1.5)(1.2)(130,000)} = 172$$
%

Next to Check Shear:

Area = 100% Heat Treat = 3.534
(Depth of 1-inch)

Area = No Heat Treat = 0.3058

PShear = (108,000) (3.534) + (70,000) (0.3058)

= 403,109

MS =
$$\frac{403,109}{(1.5)(1.2)(130,000)}$$
 = 72%

In order to check bearing of the pintle with the lunette, it is necessary to assume a minimum contact area of part-to-part. The maximum possible bearing contact area is the inner face of the large lunette eye.

Maximum Area =
$$\frac{(1.62)}{2} \frac{(2.81)}{2} = 11.23$$

If we assume 20% contact - 11.23 x 0.2 = 2.25

 $P_{Bearing} = (F_{BU}) (A)$

 $P_{\text{Bearing}} = (219,000) (2.25)$

 $P_{\text{Bearing}} = 491,874.0$

MS =
$$\frac{491,874.0}{(1.5)(1.2)(130,000)}$$
 -1 = 110%

3.3.6 Clevis

Finally, the clevis must be checked. This fitting is really a double clevis. The end toward the tow bar is a simple set of lugs.

First, the lug will be checked for tension across the net section. The material is 4140 heat treated to 180,000 Psi - 200,000 Psi. The net tension area is actually the area of the plane thru the hole centerline normal to the load but for the purpose of calculation is conservatively assumed to be twice the minimum area at the 1.15 dimension.

The Area is:

$$A = 2(1.15 - .62) (1.20) = 1.26 in.^2$$

$$P_t = F_{tu}^A$$

$$P_{+} = (180,000) (1.26)$$

$$P_t = 226,800$$

MS =
$$\frac{226,800}{(1.5)(1.2)(72631)}$$
 -1 = 73% (includes a fitting factor of 1.2)

Shear Check:

The Shear Area is:

$$A = (4) (1.39 - 0.625) (0.60) = 1.836 in.^{2}$$

 $P_{su} = F_{su}A$

= (108,000) (1.836)

= 198,288 lbs.

MS =
$$\frac{198,288}{(1.5)(1.2)(72631)}$$
 -1 = 52% (includes a fitting factor of 1.2)




FIGURE 38

Now to look at the opposite end; the tank attach clevis. The load as applied to this end causes a side load in the lugs and thus bending in the lug as shown below.




FIGURE 39

First checking the outer leg of the clevis:




FIGURE 40

Tension in the Net Section:

Area =
$$(3.0 - 1.50)$$
 (1.15)

 $= 1.7250 in.^2$

 $P_{T} = (180,000) (1.7250)$

= 310,500 lbs.

$$MS = \frac{310,500}{(1.5)(1.2)(63381.35)} -1 = 172$$
%

Shear Out of Pin:

Area =
$$2(1.50 - .75)(1.15)$$

 $= 1.725 in.^2$

 $P_{su} = F_{su}A$

= (108,000) (1.725)

= 186,300 lbs.

$$MS = \frac{186,300}{(1.5)(1.2)(63381.35)} -1 = 638$$

Now Checking Stress at Section A-A:




FIGURE 41

Area =
$$(3.15)$$
 (1.15)

$$= 3.6225 in.^2$$

$$\sigma_{\text{Total}} = \sigma_{\text{T}} + \sigma_{\text{B}}$$

$$4 = P_t = 63381.35 = 17496.6 \text{ Psi average stress}$$

 3.62

$$\mathbf{6B} = \frac{6M_2}{bh} = \frac{6(32407.8)(1.03)_2}{3.15(1.15)}$$

= 48076.4 Psi peak stress due to bending

Total = 65573 Psi due to bending, plus 17496.6 Psi average stress

= 180,000 Psi

$$MS = \frac{180,000}{(65573)(1.5)(1.2)} -1 = 538$$

Similarly checking Section B-B:

Area =
$$3.32 \times 1.48 = 4.9136 \text{ in.}^2$$

$$T = P_t = \frac{63381.35}{4.9136}$$

= 12899.17 Psi average stress

$$G_B = \frac{6M_2}{bh} = \frac{6(32407)(2)}{3.32(1.48)}$$

= 53477.28 Psi peak stress due to bending

Total = 66376.45

$$MS = \frac{180,000}{(66376.45)(1.5)(1.2)} -1 = 518$$

Next, check the Inner Leg of the Clevis:




FIGURE 42

Tension in Net Section:

Area =
$$(3.0 - 1.5) 1.0 in.^2$$

$$= 1.50 in.^2$$

$$P_t = 1.50 \text{ in.}^2 \times 180,000 = 270,000 lbs.}$$

MS =
$$\frac{270,000}{1618.65 \times 1.5 \times 2}$$
 -1 = 5,460%

Shear Out of Pin:

Area =
$$2(1.50 - 0.75)$$
 1.0

$$= 1.50 in.^2$$

 $P_{su} = F_{su}A$

= (108,000) (1.50)

= 162,000 lbs.

MS =
$$\frac{162,000}{1618.65 \times 2 \times 1.5}$$
 -1 = 3,236%

Now checking Section C-C:

$$Area = (3.15) (1.0)$$

$$=$$
 3.15 in.²

$$\sqrt{t} = \frac{P_t}{A} = \frac{1618.65}{3.15} = 513.86 \text{ Psi}$$

$$\int B = \frac{6M_2}{bh} = \frac{6 (32407) (1.03)}{(3.15) (1.0)^2}$$

Total = 64095 Psi

MS =
$$\frac{180,000}{(64095) \times (1.5) (1.2)}$$
 -1 = 56%

Finally, checking Section D-D:

$$Area = (3.32) (1.33)$$

$$= 4.4156 in.^2$$

It due to tension =
$$\frac{1618.65}{4.4156 \text{ in.}}$$
 = 366.6 Psi

$$= \frac{6 \times 32407.8 \times 2}{3.32 \times (1.33)^2} = 66220 \text{ Psi}$$

$$MS = \frac{180,000}{(66586.62)(1.5)(1.2)} -1 = 50%$$

4.0 FABRICATION

The prototype lightweight tow bar fabrication processes were chosen to fit the limited number of parts being produced. The final product is representative, however, of what a more efficient high production process would produce.

4.1 Metallic Fittings

The lug-type fittings were made as machinings from plate and bar stock of high quality military specification 4130 steel. In production, these parts would probably be near net forgings which might be finish machined in the lug area. Heat treatment of the production parts, however, would be identical to the prototype parts, (i.e., 180,000 - 200,000 PSI or 1.24×10^3 to 1.38×10^3 MPa).

The sleeves are tubular steel machined to length with an internal step and taper. No heat treatment was called out for this part.

4.2 Composite Tube

The fabrication sequence for the composite tube is shown in Figure 43.

This is a two-part process.

4.2.1 Kevlar Sheath. The sheath is made first, as it later acts as an external mandrel for the graphite/epoxy material. The process chosen for the sheath is roll-wrapping of Kevlar woven fabric preimpregnated with resin. Roll-wrapping yields a quality part with dimensionally controlled inside diameter and is a simple low cost process.

The roll wrap process (shown in Figure 43) is a mechanical procedure to deposit sheets of preoriented material onto a mandrel. The application of temperature and pressure assures good compaction as the material is deposited. The upper platen of the rolling machine is lowered by an air operated piston to make contact with the male mandrel and

exert mandrel pressure on the edge of the prepreg pattern. The bed or bottom platen of the rolling table traverses so as to cause rotation of the male mandrel thereby rolling up the prepreg. This is accomplished while maintaining pressure between the upper platen and the lower platen, so as to deposit the material in a uniform and compacted manner.

ROLL WRAP PROCESS




FIGURE 43 - Composite Tube Manufacturing Sequence

Figure 44 shows a sheath trimmed to length; ready for the next fabrication step.

4.2.2 Graphite/Epoxy Lay-Up. The mandrel for the graphite/epoxy layup is slightly undersized. It is covered by an expandable bladder which
has internal pressure fittings. The unidirectional prepreg graphite/epoxy
is laid-up on the mandrel according to the ply orientation call out
on the drawing.

The first and last plies of the lay-up are at angles of \pm 45° which give the lay-up integrity prior to curing.

The mandrel with the laid-up graphite/epoxy is inserted into the Kevlar sheath. The metallic sleeves receive the adhesive coating on the portion of the innersurface which contacts the graphite/epoxy. The sleeves are then inserted into the sheath over the graphite/epoxy covered mandrel.

Pressure is applied to the bladder over the mandrel and the graphite/
epoxy prepreg is forced out against the sheath and metallic sleeves. Heat
is applied according to the precalculated cure cycle, and the graphite/epoxy
material is cured under pressure in place against the sheath and simultaneously bonded to the metallic sleeve. Figure 45 shows a completed program
set of composite tubes.




FIGURE 44 - Sheath Trimmed to Length




FIGURE 45 - Unidirectional Prepreg on Mandrel

Summarizing the fabrication procedure is the sequence of steps presented below:

- a. Deposit Kevlar woven prepreg on the male mandrel by roll wrapping.
- b. Cure under heat and pressure applied by Tedlar film.
- c. Deposit graphite/epoxy unidirectional material on bladder covered undersize mandrel.
 - d. Apply adhesive to metallic sleeves.
 - e. Insert graphite/epoxy covered mandrel into cured sleeve.
- f. Insert metallic sleeves with adhesive into Kevlar sheath over graphite/epoxy.
- g. Inflate bladder of sub-size mandrel to expand graphite/epoxy prepreg against sheath and sleeves.
 - h. Cure with heat and pressure.
 - i. Deflate bladder and remove bladder and mandrel.

An example of an actual process document is included in Appendix A.

4.3 Weld Assembly

There are actually two weld assemblies — the tube and eye assembly and the tube and lunette assembly. The first assembles a composite tube complete with sleeves and two eye fittings. The second assembles a composite tube with sleeves, and eye fitting and a lunette fitting.

The process; however, is the same for each. The end fittings (either eye or lunette) are inserted into the sleeve of the composite tube at each of the tubes ends. Figure 44 shows an eye fitting ready for welding. The length is verified and a tack weld made through the holes in the sleeve. The length of the assembly is re-verified and the circumferential welds made around the sleeve-to-fitting junction.

Finally, the four puddle welds are finished.

4.4 Final Assembly

All parts are cleaned, prepared for painting and painted per drawing specifications. The parts are brought together per Top Assembly Drawing Number 1000 and pinned in place. A complete tow bar is shown in Figure 45.

Copies of the drawings are found in the Appendix A. These drawings are listed below:

EEMD No.	Title
100000	Tow Bar Assembly -Lightweight
100001	Tube & Eye Assembly - Tow Bar
100002	Tube & Lunette Assembly - Tow Bar
100003	Composite Tube Assembly - Tow Bar
100004	Clevis, Tow Bar
100005	Sleeve, Tow Bar
100006	Lunette, Tow Bar
100007	Eye, Tow Bar
100008	Clevis Pin, Small
100009	Clevis Pin, Large

A copy of an actual process sheet is found in Appendix E.

5.0 TESTING

Testing for the Tow Bar Program is divided into four categories:

- a. Material Testing
- b. Joint Tests
- c. Design Verification
- d. Non-Destructive Testing

5.1 Material Testing

Tests were conducted on the structural composite materials -- graphite/epoxy and the adhesive.

5.1.1 Gaphite/Epoxy. For quality control purposes, material properties are verified by material lot when received. To be used, the material tested must meet specification minimums. These minimums for high strength graphite/epoxy are:

Material Tests Used

Flexural Property	ASTM D740
Horizontal Shear	ASTM D2344
Tensile Properties	ASTM D3039
Compression Properties	አርሞል ኮንፈ10

The data from the material tests are shown in Appendix B.

5.1.2 Adhesive Testing. Tests were conducted on all the candidate adhesives to find the best. The adhesives tested were those recommended by both EEMD's fabrication staff and outside sources as being suitable for a steel to graphite/epoxy joint. These tests were conducted on a lap shear specimen using steel as one adherend and high strength graphite/epoxy as the other. With these adherends, the tests yielded allowable stress data more meaningful than the standard vendor data. The results from these tests are shown in Appendix B.

Two adhesives were chosen for further consideration during the joint tests - Narmco Metalbond 1133 and 3M AF 13. Our tests actually had slightly better results than vendor data for similar, although singular, material adherend tests.

5.2 Joint Tests

Prior to finalizing the design drawings, the proposed design for the joint was fabricated using production tooling. The part duplicated the materials and geometry in the area of the joint but it was not a full tube assembly. Also, fiberglass was substituted for Kevlar in the sheath.

The test was conducted on one-inch sections cut from the joint specimen. The test conditions are felt to be more severe than the joint will see in service, where the joint is a continuous tube which tends to resist any off-center loading moments. A sufficient length (16 inches) was allowed for the test, to prevent influence from the jaws of the test machine. Pads were added at the jaws to prevent problems. No effects due to the substitution of fiberglass for Kevlar were felt, because no bond between the steel and the sheath was made.

The results of the test show that the adhesives will withstand more than the design load in the joint configuration. The most important aspect of the joint test, however, was not a function of the adhesive. Almost all of the joint specimens failed -- not in the joint -- but in the laminate. A close examination of the test specimen showed that the interior + 45° layers of graphite/epoxy prepreg has "wrinkled" during the lay-up or pressurization, and were "prebuckled". This condition caused a local premature failure. As a result of the joint test, the laminate was changed to put these plies on the outside.

Examination of the new ply laminate showed that the wrinkling problem has been corrected. These results of the joint test are shown in Appendix C.

Both of the adhesives used in the joint tests were utilized in the final design. Metalbond 1133 was used in the interior of the tapered lap joint and 3M AF 13 was used at the joint extremes. (See the finite element analysis section for an explanation of this).

This dual adhesive approach was used on the design verification tube sent to TACOM for testing.

5 3 Design Verification

After design approval, TACOM was supplied with one item which consisted of the composite tube and the metallic sleeve.

This tube was to be tested in tension and compression to verify the design. In compression, the tube survived a load 127% greater than the design load. The tube was never fully tested in tension, due to fixture problems. Nevertheless, this test item did yield valuable proof that the process would produce a structurally sound part. The limited testing showed that the part was capable of meeting the critical strength criteria — Euler buckling stability. (See Figure 3).

5.4 Non-Destructive Testing

Ultrasonic C-Scan was chosen as the technique for non-destructive evaluation. As with all NDT, an operator evaluates the specimen and compares it to a test standard or standards. A set of standards for the tow bar laminates was fabricated. Some of the laminates were built with intentional defects of a known size, and a spectrum of possible defects and results were defined.

Some problems were encountered due to the fabrication sequence which uses the Kevlar sheath as an internal mandrel to form the graphite/epoxy tube integral with the metallic sleeve. In the area of the sleeve—to-graphite/epoxy joint, the sleeve and graphite/epoxy became an integral composite part. This allowed good sound transmission and good part definition with the C-Scan unit. In the area of the metallic sleeve, however, no attempt to bond the sleeve to the sheath was made. Because of this, the area between the sheath and the metal sleeve looks like an unbonded area and blanks out the rest of the material. After a great deal of study and trial and error, the C-Scan operator could 'read' these areas and separate out these 'voidy' regions. The results of the C-Scan studies showed that in all four tubes, no significant flaws existed. The C-Scan plots are reproduced in Appendix D.


5.5 Field Testing


Field testing of the two tow bars was conducted at Aberdeen Proving Grounds, MD., on paved, secondary, and cross-country roads. The results of this test were documented in TACOM Project No. 1-VC-080-060-123, Report No. AP6-MT-5578.


ADDENDUM


APPENDIX A


DRAWINGS




















NOTES:

- 1-MAT'L. STEEL P4140 (MIL-5.5626)
- 2-HEAT TREAT TO TENSILE STRENGTH OF 180,000/200,000 PS.I.

101 - 119 - 155

- 3-LIQUID PENETRANT INSPECTION GOOD REQD

 FR. MIL -1: LBLL 700 CAS CAC. ANTOR IN A.
 - 4- ALL SURFACES TO BE " UNLESS OTHERWISE SPECIFIED.
 - 5- SREAK SWARP EDGES.
- 4. NEAT ASSY 10001, 10002.

- \$ 000 02.1




APPENDIX B

MATERIAL TESTS

- 1. Graphite Epoxy
- 2. Adhesive

HIGH-STRENGTH GRAPHITE-EPOXY MATERIAL PROPERTIES

									200
#400MATERIALS. TESTING- TARADCOM - TOWBAR	ATERIALS. TL	ESTING- T	4RADCOM -	Тошвая	• ;	-		2/19/80	
HYE-1048-AIE	-AIE OI-	01-A-01 LOT	Lor CO-121 Rou	π/		.•			•
d 9/	16 PLIES 0°				MPRESSIVE	COMPRESSIVE PROPERTIES	TEST	- endagen dest gerendt pan introduction for control	
SPECIMEN #	9	P	P16	Spsi		* Emsi			·
)	.2512	.090	9359	865'801					
2	5445.	-0913	1861	96018	•	20.36			
c.	.2500	. 0913	2271	94,66		21.25			
→ B-3	.2504	5160.	2061	456'68		17.00			
5	.2512	6060.	2293	100,420		19.19			
		·			ALL	FAILURES	OCCURETS IN	- AT-	AREA
MEAN	·			10196	•	h.91			
S. DEV.	·			671/2				:	
•	;								
* Modalus	1	DETERMINED	FROM STRAIN	AIN GA363.					
	ę						î,		



ì .					6	4		RY THIN-ALL 4 to	1 = 1	,		cut in fab.					1014	· 66	
	ADEP OVE	•			\(\frac{1}{2}\)	33 +02		Bono LINE VERY THIN-ALL	1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1	<u></u>		er cut			-		prileag)	thes tes	
.2 -21/10P		IVE	STEEL	%01	35%	65%	%ob	%001	80%	75%	45%	1	15%	% 01	10%	10%	%02	%01	%08
14" HYF-1048- A1F KDONITE- 50	FAILURE		GRAPHITE	55 %	50%	35%	%01		2%	}	5%	}	10%	}			,)	5
	à		COHESIVE		1	}	}	1	}		1	15%	1 %59	1,700	65%	25.%	30%	30%	15%
OLVENT CLEAN	APPROXIMATE	GRAPHITE	SHEAR	35%	15%	1		•	15%	25%	ŀ	85%.	10%	%01	25%	5%	1	١	5,
ERENDS: 1/4" STEEL, BLASTED, SANDED, SOLVENT CLEANED.		Spsi		3654	3623	3657	2695	1284	4220	3336	1855	2519.	L: 4224	3572	4109	2212	3363	2815	., 2906
STEEL, BLAS	FST	AREA (IN2)		0.962	0.992	1.016	0,990	0.496	676.0	1.011	0.922	1.016	0.990	1.006	0.498	0.977	0.954	0.948	0.944
ERENDS: "		JESIVE		1 AF-13	T 808	MIN @ 350°F 5 PSI		B	.9628 ¹	- 269-10	5 ps 1	760ND	11NO 250°F	15 Psı		. QIWWNb	1-73M 7 8-298	8h52-8.77	5051

. .

APPENDIX C

JOINT TESTS

180	ES		(WAUTHESS)			(wavings)	٠		(WAVINESS)		•		
08/61/6	Notes		FAILED IN ADMESSIVE	-		FAILED IN			+ 6 % FAILED IN	(NITIATED AT METAL TIP	-	•	
	M.S.		+56 %			+18 %			+ 4 %	+ 5/13		·	
TENGLE TEST SET #	Hr. AVE SHEAR		1605			830			1039	226			·
KILL TES	P 18.		7668			1551			8208	8377			
1.FA	1 Jours	. 0	4.75"	17.8%	148-10-748	4.75"	17.75"	1440 TAB-TD-7118	1.	١			
·	d		0.299"		QISNI .	0.398"		KIRNI	. (:		>	
			1.090"			1.110"	,		1.022	1,050	20 mm	= 2 mm	5000 Je.
	imen		ADHESINE			METILBOND			. :		DRIVE =	10 SPED	ie 1500 =
•	SPECIMEN		AF-13			133	C-2		1F-13	1/33	Har.	ROSHEAD	The Soule

	<u></u>				_								
2/18/30	NOTES LAMINAIT	(WAUNESS)	(WAUNCS)	-	(WAVINESS	(w AUI ASS				. • •	bond	-Sort	
10	No	INTHATED AT METAL TIP MISSING ADMENUE	GOOD JUINT		Good Joint	EAILED PAILE					Janoth of	wf m es	
# 2	WS.	126%	201.1		3.2%	93%	• •				oven 8, 2	eh of sor	VI ARSS
1EST SET	Aug Syfore	1453	13512		1234	0721	-			•	due to thomat storsses Approx/2 meh over 8.2 Sangth of bond:	shortened to within 1/2 inch of sourt	e to waviness
TENSILE TH) Js.	13,228	0/.9/11	·	11,839	362'11	-		·		doll sass.	ed to wi	lone due
7	Jourt.	<i>"b</i>	.6		. 6	6			•	•	enmal stre		laminate failure
	P	0,29	0,29		0,30	0,30	•		= 11.5"		due to th	test langth	.
	9	1.7.1	1.05	•	1.17	1.16			46 to tab =		1) Curvature	Secons to	to simulate
	SPECIMEN	AF-13 ADMISSIVE	2 AF-13 ADMECIVE		1133 AIMALDONO	1133 METALZONZ		•	length uside t	0	Notes 1) C	2) 3	+
			7				C-3	İ	97.				1

APPENDIX D

C-SCAN RESULTS

Figure 37

TACOM TOWBAR

SCARF · JOINT C-SCAN

DATE 12-10-80

TUBE	SN3	XDCR TYPE	2.25 mHZ TRANS.	1 .50" 5.0 mHz	REC. MODE	THRU TRANS	MISSION
ENFRG	y <u>2</u>	GAIN 408	ATTEN ~ 10 d8	GATE WIDT	H 10NS	GATE DELA	Y AS REO'D

RESULTS - COMMENTS - (A): NO SIGNIFICANT FLAWS

INDICATED IN THE GRAPAITE STEEL INTERFACE

ONE LARGE AND SEVERAL VERY STABLL

INDICATIONS WERE FOUND IN THE MEVICAR |

STEEL BOND AIREA. THESE WERE


RE-EXAMINED BY PULSE-ECITO A. SCAN.

RESULTS - COMMENTS - B: NO SIGNIFICANT


FLAWS INTICATED IN THE BRADHITE!

STEEL BOND AREA. DISCONTINUITIES

GXIST IIU THE KEULAR STEEL BONDARE



JOINT A



JOINT 8

D-2

Figure 38

TACOM TOWBAR SCARF JOINT C-SCAN

DATE 12-9-80

TUBE SH	5 XDC	R TYPE .50" 2.251	NHZ TRANS. O	.50° 5.0 MHZ	REC. MODE	THRU TA	ANSMISSION
ENFRGY	2 GAIN	40dB ATTEN	~ 10 d8	GATE WIDTH	IONS	GATE D	ELAY AS REO'D

D-3

RESULTE - COMMENTS - A: JOINT A) CONTAINED NO

SIGNIFICANT DISCONTINUITIES IN THE

GRAPHITE STEEL INTERFACE. ALL OF

THE INDICATIONS WHICH ARE SADWN

BELOW ARE IN THE KEVLAR STEEL INTERFACE. THIS WAS VERIFIED USING AUSE
ECHO A-SCAN. THIS JOINT WAS SCANNED

IN INCREMENTS RANGING FROM 1/2" to

9/16" WITH AN INDEX INCREMENT OF .020".

RESULTS - COMMENTS - (B): NOINT B CONTAINS A

SIGNIFICANT DISCONTINUITIES ANTHE,

GRAPHITE/STEEL INTERFACE. ALL OF TH.


INDICATIONS SHOWN BELOW ARE IN TH

KEVLAR /STEEL (KK) OR KEVLAR/GRAPA


(K/G) INTERFACE. NO SIGF WICANT

VOIN OR DELAMINATIONS IN THE

GRAPHITE.



, JOINT A'



JOINT B

Figure 39 TACOM TOWBAR

SCARF · JOINT C-SCAN

n a		

TUBE	SN 6	XDER TYPE OF	o" 2.25 mmz Traus.	1 .50°	5.0 MHZ REC.	MODE_	THRU TRANS	MISSION
ENERS.	, 2	GAIN 4088	ATTEN ~ 10 dB	GATE	WIDTH TON	5 6	SATE DELA	Y AS REO'D


D-4

RESULTS - COMMENTS - A: NO SIGNIFICANT FLAW
INDUCATIONS IN THE STEEL/GRAPHITE


BOND AREA. INDUCATED BELOW ARE
THE DISCONTINUITIES EXISTING IN
THE KEULAR/STEEL AND KEULAR/
BRAPHITE AREAS.

RESULTS - COMMENTS -B:

NO SIGNIFICANT FLACU INDICATIONS
COULD BE FOUND IN THE GRAPHITE/STEEL
BOND AREA. MANY SMALL, INTERCOLLECTE
DISCONTINUITIES EXIST IN THE LECULAR!
STEEL BOND.



JOINT A



JOINT B

Figure 40 TACOM TOWBAR

SCARF · JOINT C-SCAN

DATE 12-11-80

Tube sh 7	XDCR TYPE OF Z.25 MHZ TRANS.	1.50" S.ONHZ REC. MODE	THRU TRANSMISSION
ENERGY 2	GAIN 4048 ATTEN - 1048	GATE WIDTH TOUS	GATE DELAY AS REO'D

D-5

RESULTE - COMMENTS - A : HOINT A HAD NO SKNIFKANT

DISCONTINUITIES IN THE GRAPHITE/STEEL BOND

AREA. SEVERAL DISCONTINUITIES EXIST

IN THE KEVLAR/STEEL AND KEVLAR/BRAHITE

BOND. THESE WERE RE-EXAMINED

USING PULSE-ECHO A-SCAN

RESULTS - COMMENTS - B: JOINT B HAD NO

SIGNIFICANT DISCONTINUITIES IN THE


GRAPHITE/STEEL BOND AREA. INDEATED *

BELOW ARE THE AREAS. IN WHICH THE


KEULAR/STEEL OR KEWAR/GRAPHITE ^

BOND WAS NOT CONTINUOUS. THESE WERE

VERIFIED USING PUSE.ECHO A-SCAN.



JOINT A



JOINT B

APPENDIX E

PROCESSING

MANUFACTURENG FROCLSS SHEET

FRAFTEK/ EXXON ENTERPRIL


Pren	ared D	Qiantit	ياً ما يان No.	Dwg. No.	REV.	D+ No 30000		M. 6 - D	
Shaft			Pt. No. 10003	•	Mfg Proc 0121	No. REV 0			
398 10003					E.O.	REV.			
6.5	1. Eng. Approval QC. Approval Proj. Eng. Approval S/N(s) TL Dwg # Cust & TAR							TARADCOM/	
		JIN 5/2	3/80 /	Holenson	16	REV.	Pt Descr.	· Tow Bar S	haft
		MATER	IALS	7	······································		NOTES	3	
01-4	-01 (CM	S 100. Fiberi	LO UVE 1	046 235)				<u></u>	
LOT	C1-1	ru	MFO		0				
				// //					
Roce)	<u> </u>						
R.C	.36	6, 6	1						
Oper.			!					<u>-</u>	1 2-1-
No.	Dept No.			OPERATION	DESCRI	TPTION		Stan	Date Time
		This part	will be	made on a ru	bber co	vered mandrel.	The rubber		Malak
01	663	bag must b	e checke	d for leaks.		· · · · · · · · · · · · · · · · · · ·		JAN	X7/8/80
	1								
		Use clamps	to seal	the ends of	the m	bber bag against	the tool	1	
05	663	Protect th	e rubber	bag from be	ing cut	by the hose cla	amps by		
		wrapping t	he rubbei	bag with N	ylon ta	pe or scrap rubb	er in the		11 10
		area where	the hose	clamps wil	l be lo	cated.		1/11	
- 1				·			·	19:3	
									
20	663	Apply about 3-5 psi to the inside of the rubber bag through the							,
ヘゴ	air fitting on the end of the mandrel. Brush a solution of . liquid soap(about 60% water, 40% soap) mixed with water over the							e .	1
	entire surface of the rubber bag. Soap bubbles indicate air								
1	leakage. Mark any air leaks clearly with permenant ink. See						///	1. 20	
	Manufacturing Engineering for an Operation Process Sheet on Rubber Bag Fabrication and Repair if necessary.								4
Į.	- }	Rubbel Bag	Fabricat	ion and Repa	111 11	necessary.			,
		Layout rubber bag as shown in Sketch #1. Use a ball point pen.							
15	663								
[J	Wrap rubber bag with .001" thick teflon film in the 68.02" area							
20	663	between Mark 1 and Mark 4 (Sketch #1). Double backed tape should be used to secure film. The wrap must be 15 turns, not butt							+
1	- F	jointed.	secure I	IIm. The wr	ap musi	be 15 furns, no	of buff		1
						DOUBLE			•
						BACKED	HONOZEL	JFILM	
25	663 L	Cut pattern	s per Ske	etch #2.					racked Dangle
	003	Tay-un nor			Cleana	#2 Wrim on sh			APE
Lay-up per stacking sequence in Sketch #2. Trim each pattern to 80 663 wrap around the lay-up making a butt joint. No overlaps are						W/#	<u> </u>		
						eption of the fi		n.	T -
	$-\!$					to get the firs			
1	to stay in place. A heat compaction is called out on Sketch #2								
	at plies 17 and 36. To heat compact, use the Tedlar winder to compact the part with nylon tape. Put the mandrel in oven for							 	
ı	20 minutes at 150°F. Remove part from oven, remove nylon tape]
		being caref	ul not to	disturb la	minate,	and rewrap with	nylon	1/1/	11
						must be centere		1/1/	11/
1	-	relation to ±45° patterns				el within .050".	Seams on	'- /	1
		-42 Parterus	o are co	<u>~~ 5taoom</u> ed	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				

("NUFACTURING PROCESS SHEFT. GRAFTEK/ EXMON ENTERPRISEL

		•		-					
per No	Dep	OPERATION DESCRIPTION	St	атр	Dai Tir				
		Sand inside of kevlar sleeve until visibly rough. Clean with							
35	663	acetone. Use 80 grit aluminum oxide sandpaper.							
·	-}	Check fit of end fittings on lay up. They should slide on far enough	7		 				
40	663	to achieve a total length of 69.48 ± .02" end to end	1						
**		69-52 ok GKR							
:	<u> </u>			4.4	<u> </u>				
45	663	Sandblast inside of two steel end fittings. Clean entire end fitting with tricholoethylene. Handle parts with clean gloves only after	N		& 2:				
	+	cleaning. Apply metlbond 1133 (03-A-01) and AF-13 to Electe per	2/14	* 	2/10/				
		sketch below. See Manufacturing Engineering for AF-13. Leave pro-			1/48				
		tective films in place on adhesive. It may be necessary to warm end			7				
	<u> </u>	fittings to get the AFELS to Stick.							
	 	14-5.85"± .1"→1							
•									
	<u> </u>								
	1	GRAPHITE LAYUP AF AF AF	:						
	 .								
	ŧ				•				
		1123							
		\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \		_					
			1	. [
	,								
			$\perp L$						
		TAPENED AREA OF	$\neg \cdot \cdot$		•				
		GRAPHITE LAYUP NO GRAPUITE							
	•		- [".						
	 	9.85 z. 1 "	1						
. 1	ŀ		/						
		Check fit of sleeves on lay up. They should slide on far enough	1/1	1	1				
50	663	to achieve a total length of 69.48" ± .02" end to end.	KU		<u>)'</u>				
				.					
		(NEON SLEEVES THOROUGHLY WITH ACETONIE .							
55	663	Assemble sleeves into keylar cover. Measure total length. Total length should be 69.48" ±.02" end to end. Mark the actual total		-					
77	003	length should be 69.48"02" end to end. Mark the actual total							
		the cover with sleeves attached can be located properly over the	M	,					
•	L	(lay up. MARY LOCATION OF KEVIAR CONFILENO ON EXTLYFEVE							
_ '-		Mix a small amount of Ren Fast-Weld No. 10. Spread a thin coat		- -					
60	663								
		in a 1" wide band on the in-hoard side of the mark made in Operation Immediately insert1sleeve fully into kevlar cover. Clean off any							
	<u>.</u>	excess. Hold together tightly for 5 minutes # 1 minute. This	W	14	/				
	. -	operation must be performed rapidly as Fast-Weld No. 10 has a pot life of only 4 minutes. The purpose of this operation is to prevent the	,						
		sleeve from shifting during subsequent operations.and seal the joint	in us	e.					

C'ANUFACTURENG PROCESS SHEET: : GRAFTEK/ EXMON ENTERPRISE:

er	- Dept			7.7.
<u>ار</u>	No.	OF EIGHTON DESCRIPTION	Stam	p Da Ti
55	663	Remove the protective covering from the adhesive of the leaves. Slide the kevlar cover with one sleeve attached into position over	1/1/	17/2
		the lay up. Check fit of second sleeve.	- 71/2	
70	663	Repeat Operation 60 and bond second sleeve into keylar cover	161	11
75	663	Insert a thermocouple wire under each sleeve. Wrap mylar tape around	1	1
	1 005	wire end to prevent the wire from puncturing the rubber bag. DO NOT GET THE WIRE BETWEEN THE GRAPHITE AND THE SLEEVE.	ald	11
30	663	Shim the sleeves using nylon tape, rubber, etc. so that they are concentric with the lay up.		
			- Stall	10
35	663	Wrap mandrel, rubber bag and kevlar cover with nylon tape. Firm tension should be used, but not so tight as to distort kevlar Cover. Be sure to let thermocouple wires stick out use he averland	1	
		cover. Be sure to let thermocouple wires stick out.Use 2" overlap.	400	11
30	663	Apply hose clamps at each end of rubber hag, OVER DYLON WORR.	Pal	(/
25	663	Wrap a second layer of nylon tape over everything. LEAVE HOLE CLAMP SURENS EXPOSED,	<u> </u>	
0	663	Put in oven and apply 85 psi ± 5 psi. Listen for air leaks DO NOT SET ON OVEN FLOOR AS HEAT UP RATE IS TOO SLOW ON FLOOR.	MIL	9/15/2
·				
.05	663	If no leaks are present, hook up temperature recorder and raise part temperature to 250°F ± 5°F. Hold at this temperature for a minimum of a hours.	flel	11
		8	,	
.10	663	Cool under pressure to below 175°F.	ME	1/
115	663	Remove processing materials. Remove part from mandrel Wrap mandrel with a protective layer of nylon tape and store.		
120	663	Submit part, Operation Process Sheets and Cure Chart to inspection.		
125	668	Inspect per print.		*
一				
				-
			·	
`		E-4		
_				·
•	•	·	1	



SKETCH #

			•		,	•	
	PATTERN No.	PLY NO.	ORIENT- ATION	WIDTH OF PATTERN	LOUGH LENGTH OF PATTELN KURCHMFELENC	COMPACT	
•	PATTERNZ PLES ON TOOL	PLY 36 PLY 35	+45	44,72"± 05"	<u> </u>	HEAT COMPACT	211-+150
3	PATTERN 2 PLIES ON TOOL	1	+ 45	44.91't.05"	14"		24-±150 28-0
N.	FIT TPLY,	7	0	45.72" I.05"	14"		IMMMMMIN .
1 2	PATERN, 2	Jan. 0.1	0	4672"±05"	14"		
×	#15 2 PLY PATTERN 2. PUES ON	PLY 29	0	47.72"=.05"	13/2"		urilmil
	TOOL = 14 2 PLY	PLY 28	0			COMPACT	
\times	PUESON TOOL	PLY 26	0	48.92"±25"	13/2" -	,	
X	#13 2 PLY DATTERN, 2 PUES ON TOOL	PLY 25 PLY 24	0	49.92±.05"	13/2"	,	
\times	#12 2 PLY PATTERN 2 PLES ON	PLY 23	D	50.92±.05"	134"	·	cut + cay.
× .	FIT 2 PLY POTTERN, 2	PLY 22 PLY 21	0		13/2"		16+19.
\times	TOOL FID 2 PLY PATTEEN 2	PLY 20 PLY 19	0	53.12"±.05"	13",		
· •	HO O OV	PLY 18	0		13"	HEAT -	
$\boldsymbol{\varkappa}$	PATEIN, 2 PUES ON TOOL	PCY 10	0	54.12"±.05"	13"	COMPACT	
	#8 2 RY .	PLY 15 PLY H	0	55.72"±.05"	13"		
	F7 2 PLY PATTEON, 2	PLY 13	0	57.32"±.05"	13"		
`\.	Tool	PLY D.	0	58.92"±05	13",	(-	
1	TOOL	PLY 10	8			COMPACT	* · · · · · · · · · · · · · · · · · · ·
$\sim \times 1$	PATTERN;2	PLY 9 I	0	60.52"±.05"	12%		FINISHED PART
\rightarrow	PY ON TOOL	PLY 7	0 (62.12"±.05".	124"		
X		PLY 6 PLY 5	0	62.12"±.05"	121/2"	·	-45 A+45
*	\$2 2 PLY PATTERN, 2 PLIES ON T	PLY 4	- 45 + 45	62.12"±.05"	21/2"	-	-
× 15	FI 2 PLY F	LY 2	- 45 - 45	62.12"±.05"	12/2"		•
	100 11	TOOL	SUILF	ACE E-6			
						•	


MUNUFACTUREIG FROCESO CHEÈT

GRAFTEK/ EXXON ENTERPRIS


Sheet 1 of 4

Gran	pared B nt Robi	son	373 001 373 001	Dwg. No. Cover 10003	REV	Pt. No. :	10003 REV.	Mfg Proc No 0114 +	_		
及	Eng.App	oroval QC. Appro Smg4il 5/14/60		following /80	S/N(s) B	TL Dwg # T-SK-10003	Cust & Pt Descr	TARADCOM/ tow bar to	ube cove		
		MATER	IALS	//	•		NOTES				
FIBE	RITE M	XM 7701/281	1			1. READ ENT	IRE PROCESS BE	TODE CHADATA	30		
							lat'l Lot No		¥(5.		
							Roll No				
						3. Roll wei 4. Roll wei	ght before cut ght after cutt	ting.			
: 4						1011 WC1	gire arcer cure	1119.			
Opėr No.	Dept			OPERATIO	N DESCR	IPTION .		Stamp	Date Time		
	653/	Entirely di	sassembl	e mandrel a	nd clea	n thoroughly	with acetone.	Mul	T		
01	663	reassemble.	 						_ <u>% Now</u>		
	1							·	1		
	653/	Wipe two co.	ats of D	C-20 Mold Re	elease(69-A-03). Ci	ure coating for	- 11.00			
05	663	two hours i	n a 375 ⁰	F oven.				- JUL	1.		
	1								1		
	653/	Apply one co	oat_of_R	AM 225 to ma	andrel.	Air dry 10	minutes	11.0	1		
10	663	Buff lightly	y. Appl	y second coa	at of R	AM 225. Air	dry 10 minutes	all	1"		
		buff lightly	7.		····						
- (3) -	653/	Cut patterns	ner ska	atch #1				1100	 		
15	653/ Cut patterns per Sketch #1.					- dle	"				
20	653/		le build-	up patterns	per s	ketch #2. Tr	im ends to for	m			
20	b.ct joints. Apply 1.5" wide build-up patterns per sketch #2 with seams 180° from previous ply. Trim ends to form butt joints.						 				
						•		Meller	11		
25	653/	CENTER MANG	PORT OF	PATTEEN. MA	teon of	MANDEEL G	OF WRAP ON MAN DER EXETCH WITH	DVE.			
25	663	とミロか のつりぞの	m PREV	IDUL PIY A	UTT FC	OUF OF SWAI	il part of over	N /	 		
		AFTER COLLIN	JG TRIM	PATIERN	EXX.	ARALLEL TO	VANDREL CENTE	ON MANOREL. WILL " 24.			
		LINE TILIM	NED EC	E MUST	MATCH	SIACTING N	محتريد,				
	653/										
30	663	Compact lay-	at 1500p	± -10°F Re	emove.f	rom-over and	en for 20 minus remove nylon t	tes WW	11		
•	-1										
	653/	Compact large	un with		NSE 12"		le wire under				
35	663	tape at each	end of	part. Attac	ch ther	mocouple wire	es to temperati	ire			
•	Ĺ	recorder. R	ecord th	e following	inform	ation on tem	perature chart,				
		Part number,	serial	number, date	e and t	ime of cure,	chart speed,	100			
.	}	job number ar at 260°F ± 10		or initials	Cur	e for 120 mir	utes 15 minut	es			
	653/			rt. Route r	part an	d operation t	process sheet	1110			
40	40 663 to Machine Shop for trim. Part must be kept free of oil and crease.					selle	11				
	.	•									
		Trim part pe	er sketch	1 #3.				1211	16		
45	662	Route part an	nd operat	ion process	sheet	to lab.		表は	11		

SKETCH #1



Sheet 3 of



DISTRIBUTION LIST

	COPIES
Administrator Defense Technical Information Center ATTN: DTIC-DDA-1 Cameron Station - Bldg 5 Alexandria, VA 22314	12
Commander US Army Tank-Automotive Command ATTN: DRSTA-TSL Warren, MI 48090	2
Commander US Army Tank-Automotive Command ATTN: DRSTA-NF Warren, MI 48090	1
Commander US Army Armament Materiel Readiness Command ATTN: DRSAR-LEE-D/Mr. Cahill Rock Island, IL 61299	. 1
Director US Army Materials and Mechanics Research Center ATTN: DRXMR-M Watertown, MA 02172	1
Ciba-Geigy Riggs Engineering Dept 8245A Ronson Road	1